

AD-A033 239

DUMONT ELECTRON TUBES CLIFTON N J
STUDY AND IMPROVEMENT OF THE S-1 PHOTOEMISSIVE SURFACE.(U)
SEP 67 H TIMAN

F/G 9/1

DA-44-009-AMC-1811(E)


UNCLASSIFIED

ETC-380-67

NL


| OF |

AD
A033239



END

DATE
FILMED
1-77



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

ADA 033239

UNCLASSIFIED

~~CONFIDENTIAL~~

ETC-380-67

COPY 1 OF 23

⑨ Quarterly (3rd) rept. no. 9,
1 Feb - 30 Apr 67,
THIRD QUARTERLY REPORT NO. 9.

~~FOR~~

⑥ STUDY AND IMPROVEMENT OF THE S-1 PHOTOEMISSIVE SURFACE, (U)

THIS REPORT COVERS PERIOD 1 FEBRUARY - 30 APRIL 1967

⑩ Hans/Timan

⑫ 24 p.

DDC
RECEIVED
DEC 8 1976
A

DU MONT ELECTRON TUBES, A DIVISION OF FAIRCHILD
CAMERA AND INSTRUMENT CORPORATION
750-760 BLOOMFIELD AVENUE
CLIFTON, NEW JERSEY 07015

DISTRIBUTION STATEMENT A

Approved for public release;
Distribution Unlimited

UNITED STATES ARMY ENGINEER
RESEARCH AND DEVELOPMENT LABORATORIES
FORT BELVOIR, VIRGINIA

⑮ DA-44-009-AMC-1811(E)

⑪ 12 Sep 1967

This document contains information
affecting the National Defense of
the United States within the meaning
of the Espionage Laws, Title 18,
U.S.C., Sections 793 and 794, its
transmission or the revelation of its
contents in any manner to an un-
authorized person is prohibited by law.

DOWNGRADED AT 3 YEAR INTER-
VALS; DECLASSIFIED AFTER
12 YEARS.
DOD DIR 5200.10

CL 31699

UNCLASSIFIED

118460

~~CONFIDENTIAL~~

UNCLASSIFIED ~~CONFIDENTIAL~~

TABLE OF CONTENTS

PAGE

PART I:

PURPOSE	2
GENERAL FACTUAL DATA	2
DETAILED FACTUAL DATA	2

PART II:

PROGRAM FOR THE NEXT INTERVAL	6
-------------------------------	---

PART III:

MEETINGS, CONFERENCES	7
-----------------------	---

SUPPLEMENTARY

TABLE I - ELECTRICAL PROPERTIES OF TUBES PROCESSED DURING THE QUARTERLY PERIOD 2/1/67 - 4/30/67.	8-9
---	-----

FIGURES 1-24.

PREPARED BY: Hans Timan, Project Engineer
RELEASED BY: Alan Howell, Contract Administrator
DU MONT CONTROL DOCUMENTS: SI-6384, T6-2018, MO-10198

ACCESSION NO.	
DTIC	UNCLASSIFIED
DDI	CONFIDENTIAL
UNCLASSIFIED	
JUSTIFICATION	
BY <i>Butler in file</i>	
DISTRIBUTION/AVAILABILITY CODES	
Dist.	AVAIL. AND/OR SPECIAL

UNCLASSIFIED

~~CONFIDENTIAL~~

UNCLASSIFIED

~~CONFIDENTIAL~~

PART I - PURPOSE

Under this contract, photoelectric emission of the S-1 surface is being studied. Specific aims are:

1. Increase of white light sensitivity to 100 $\mu\text{a/l}$ for 2870°K.
2. Reproducibility of processing schedules for high sensitivity cathodes.
3. Lowering of the thermionic emission to a value of 10^{-13} A/cm² or less.
4. Measurement of physical and optical surface properties.

PART I - GENERAL FACTUAL DATA

A. Tube processing during the month of April

During the month of April, 19 tubes were assembled, 12 of which attained cathode processing status.

PART I - DETAILED FACTUAL DATA

During the month of April, the high infrared processing method described in previous reports was further investigated. The attempt to improve response at 10600R by means of selective oxygen exposure were successfully continued and some very good results were achieved.

UNCLASSIFIED

~~CONFIDENTIAL~~

CONFIDENTIAL

All surfaces with numbers below 0-200 were processed on 7052 glass, while all numbers above 0-200 refer to a new batch of 7056 glass.

During April, the high infrared processing technique was used in 10 tubes, Numbers 0-165, 0-171, 0-174, 0-201, 0-202, 0-203, 0-204, 0-206, 0-207, 0-208. Of these, 7 attained good or excellent surfaces. Nos. 0-202, 0-203, had the highest and third highest infrared sensitivity value ever processed; this high level is also reflected in the very high response figure at 11500Å. Nos. 0-165, 0-176, 0-204, showed severe slump after completion of the processing. The reason suspected is poor adherence of the Cs to the Ag-base, as in all these surfaces, "bake-off" of the Cs took place during the processing bake. Two attempts were made to introduce other alkalis for doping purposes into the high infrared process; however, all these attempts have, so far, been unsuccessful and resulted in poor cathodes.

B. Summary of work performed during the 3rd Quarterly Period

During this period, again the major effort was expanded towards further refinement of the high infrared processing method. In addition to the previously explained and described processing steps, it was

CONFIDENTIAL

CONFIDENTIAL

tried to optimize response at 10600Å for future application in image devices. This was achieved by dosing final oxygen exposure with a monochromatic filter (10600Å). It was found that this resulted undoubtedly in strong increases in the response between 1.0 to 1.2 μ . This is reflected in the unusually high percentage of infrared response measured on many surfaces. Nos. 0-202, 0-203, 0-142, 0-136, 0-208, all had 2540 sensitivity above 10 μ A with percentages as high as 18% of the luminous sensitivity. All these sensitivities are higher than any results reported by us or elsewhere.

Detailed results are given in Table I (For details on tube processing see also Rpts. 7,8). Spectral response curves of the tubes of interest are given in Figures 1-14.

From Table I several interesting conclusions can be drawn:

1) While luminous sensitivity figures are still in the 50-70 μ A range, the spectral distribution has been changed by pulling down response in the .6 - .9 μ range while increasing response around 1.0 μ and extending the threshold. This "compensation" of spectral response has been discussed frequently in the reports of the previous contract (See e.g., Final Report, AMC-136(T), pgs. 32-33).

CONFIDENTIAL

CONFIDENTIAL

2) Nearly all surfaces with good response at 11500Å have relatively low resistance figures ($< 2 \times 10^6$). Compare also Rpt. No. 3, Table I, of this contract. This correlates possibly with a generally slightly thicker Ag-baselayer (55-65% coverage instead of the usual 45-55% coverage).

3) Dark current is strongly increased together with extended infrared response. It is remarkable that those surfaces which have a high infrared response with low white light luminous sensitivity invariably have very high thermionic emission, usually much higher than surfaces which have high luminous and infrared sensitivity. This observation has also been made previously with different processing schedules. A satisfactory explanation for this fact is not available.

"Doping" attempts with other alkali metals to lower thermionic emission have, generally, been unsuccessful in this method (Possible exception, No. 0-157, See Rpt. No. 8, p. 3).

Undoubtedly, the effect of a dopant for lower thermionic emission is contrary to the development of high infrared sensitivity and will be difficult to establish.

CONFIDENTIAL

CONFIDENTIAL

We were also not yet able to gain a better insight into the mechanism which accounts for the observations made during the "Cs-bake" after the Cs drift. Attempts to study this phenomenon in "slow motion" on tubes with attached ion pump and oxygen supply have not resulted in performance similar to the more standard procedure.

Some additional experiments with cooling and heating the glass substrates have confirmed the conclusions drawn in the last quarterly report (No. 6). None of those preparation techniques have shown promise of good and stable cathode formation (again possibly excepting the region below -10°C which will be investigated further at a later date).

Although planned for this quarter, dielectric substrates have not been prepared as yet for cathode studies, because of the preference given to further experimentation with the high infrared processing technique.

PART II - PROGRAM FOR THE NEXT INTERVAL

1. Further investigation of the high IR processing method with particular consideration of establishing criteria of the Ag-base for successful application of this method.

CONFIDENTIAL

CONFIDENTIAL

2. Study of doping techniques to suppress high thermionic current on high infrared cathodes.

3. Study of the preparation of dielectric substrates for application in the semi-transparent mode.

4. Continuation of optical measurements to determine optical constants on a representative sample.

PART III - MEETINGS, CONFERENCES

On February 17, 1967, H. Timan visited the ERDL Laboratories. Status of the program was reviewed with G. Burroughs and Dr. H. A. Stahl. A discussion about the application of high infrared processing techniques in image tubes was conducted with J. Johnson and members of the image tube group.

On April 11/12, Dr. H. A. Stahl visited these laboratories for program review and discussion. Demonstrations of processing techniques were given.

CONFIDENTIAL

CONFIDENTIAL

TABLE I (CONT'D)

ELECTRICAL PROPERTIES OF TUBES PROCESSED DURING THE QUARTERLY PERIOD 2/1/67 - 4/30/67

Tube No.	Processing Date	Luminous Sensitivity in $\mu\text{A/L}$ WL	Thermionic Emission in $\text{A/cm}^2 \times 10^{12}$	Absolute Sensitivity in mA/W				Resistance in Ω/\square
				4535R	6015R	9500R	11500R	
0-153	3/21/67	52	-	-	-	-	-	-
		Severe slump						
0-154	3/15/67	59	8.0	1.8	3.3	2.6	.07	1.0×10^9
0-157	3/23/67	50	1.2	1.8	2.7	1.8	.19	1.8×10^6
0-165	4/24/67	50	-	-	-	-	-	-
		Severe slump						
0-171	4/12/67	53	40.0	2.4	3.8	1.9	.15	7.5×10^9
0-201	4/22/67	46	100.0	1.8	2.7	1.4	.18	1.8×10^5
0-202	4/20/67	69	9.5	3.0	3.4	2.3	.41	4.0×10^5
0-203	4/20/67	53	20.0	2.7	3.1	1.8	.38	5.0×10^4
0-206	4/27/67	50	4.2	1.6	2.9	2.0	.05	1.5×10^6
0-208	4/28/67	64	13.0	3.7	4.7	2.0	.27	1.5×10^7

CONFIDENTIAL

CONFIDENTIAL

TABLE I

ELECTRICAL PROPERTIES OF TUBES PROCESSED DURING THE QUARTERLY PERIOD 2/1/67 - 4/30/67

Tube No.	Processing Date	Luminous Sensitivity in $\mu\text{A/L}$		Thermionic Emission in $\text{A/cm}^2 \times 10^{12}$	Absolute Sensitivity in mA/W			Resistance in Ω/L
		WL	2540		4535R	6015R	9500R	
0-127	2/01/67	46	5.3	3.0	3.6	3.3	1.0	.08
	5/08/67	Very low						
0-132	2/03/67	51	6.6	22.0	3.0	2.9	1.3	.16
	5/08/67	39	5.5	"	"	"	"	"
0-134	2/10/67	55	6.1	5.5	"	"	"	"
0-135	2/13/67	43	4.1	"	"	"	"	"
		Severe slump						
0-136	2/21/67	73	10.2	27.0	3.2	4.1	2.7	.22
0-138	2/24/67	37	5.1	66.0	2.0	2.4	1.3	.20
0-141	2/28/67	37	8.2	42.0	1.5	1.3	1.2	.23
0-142	3/02/67	68	12.0	28.0	2.1	3.3	2.4	.38
0-143	3/02/67	58	7.3	1.8	2.2	3.5	2.2	.06
0-145	3/06/67	44	8.0	66.0	1.5	1.9	1.6	.25
0-151	3/20/67	36	7.4	4.8	1.3	1.9	1.5	.03
0-152	3/21/67	41	8.0	110.0	1.7	2.1	1.5	.28

-continued-


CONFIDENTIAL

NO. 340R-20 DIETZGEN GRAPH PAPER
20 X 20 PER INCH

EUGENE DIETZGEN CO.
MADE IN U. S. A.

CONFIDENTIAL

SERVOVAL RESPONSE CURVE
FOR WIDE BAND SYSTEM
RUN NO.: 1459
DATE: 2-11-67



CONFIDENTIAL

FIGURE NO. 1

NO. 340R-20 DIETZEN GRAPH PAPER
20 X 20 PER INCH


EUGENE DIETZEN CO.
MADE IN U. S. A.

CONFIDENTIAL

SPECTRAL RESPONSE CURVE
FOR TUBE NO. EX-01112

RUN NO.: 1113

DATE: 4/11/47



CONFIDENTIAL


.3 .5 .7 .9 1.1 1.3

NO. 340R-20 DIETZGEN GRAPH PAPER
20 X 20 PER INCH

EUGENE DIETZGEN CO.
MADE IN U. S. A

CONFIDENTIAL

SPECTRAL RESPONSE CURVE
FOR TUBE NO. EM-0143
RUN NO.: 1184
DATE: 4-5-67



CONFIDENTIAL

NO. 340R-20 DIETZGEN GRAPH PAPER
20 X 20 PER INCH

EUGENE DIETZGEN CO.
MADE IN U. S. A.


CONFIDENTIAL

SPECTRAL RESPONSE CURVE

FOR TUBE NO. SE-0145

ITEM NO.: 1105

DATE: 4-17-67



CONFIDENTIAL

NO. 346R 20 DIETZGEN GRAPH PAPER
20 X 20 PER INCH


EUGENE DIETZGEN CO.
MADE IN U. S. A.

CONFIDENTIAL

SPECTRAL RESPONSE CURVE
FOR TUBE NO. 1E-0151

TUBE NO.: 1186

DATE: 4-17-67



CONFIDENTIAL

EUGENE DIETZGEN CO.
MADE IN U. S. A.

NO. 34DR-20 DIETZGEN GRAPH PAPER
20 X 20 PER INCH

CONFIDENTIAL

SPECTRAL RESPONSE CURVE
FOR TUBE NO. MK-0152
ROW NO.: 1187
DATE: 4-17-67

100

80

60

40

20

.3

.5


.7

.9

1.1

1.3 μ

CONFIDENTIAL




NO. 34DR-20 DIETZEN GRAPH PAPER
20 X 20 PER INCH

EUGENE DIETZEN CO.
MADE IN U. S. A.

CONFIDENTIAL

SPECTRAL RESPONSE CURVE
FOR TUBE NO. W-0151
RUN NO. 1188
DATE: 4-17-67



CONFIDENTIAL

FIGURE NO. 7

.9

.7

.5

.3

1.1

1.3A

NO. 340R-20 DIETZGEN GRAPH PAPER
20 X 20 PER INCH


EUGENE DIETZGEN CO.
MADE IN U. S. A.

CONFIDENTIAL

SPECTRAL RESPONSE CURVE
FOR TUBE NO. EX-0157

RUN NO.: 1189

DATE: 4-27-67




CONFIDENTIAL

FIGURE NO. 8

CONFIDENTIAL

SPECTRAL RESPONSE CURVE
FOR TUBE NO. XI-0171
TUBE NO.: 1197
DATE: 7-3-67




CONFIDENTIAL

NO. 340R-20 DIETZEN GRAPH PAPER
20 X 20 PER INCH

EUGENE DIETZEN CO.
MADE IN U. S. A.

CONFIDENTIAL

SPROTRAL RESPONSE CURVE
FOR TUBE NO. 8A-0201
RUN NO. 1198
DATE 7-3-67




CONFIDENTIAL

NO. 340R-20 DIETZGEN GRAPH PAPER
20 X 20 PER INCH

EUBENE DIETZGEN CO.
MADE IN U. S. A.

CONFIDENTIAL

CENTRAL RESPONSE CENTER
FOR RUM NO. 11-0-000
RUM NO. 1194
DATE 5-23-67




CONFIDENTIAL

EUGENE DIETZEN CO.
MADE IN U. S. A.

NO. 340R-20 DIETZEN GRAPH PAPER
20 X 20 PER INCH

CONFIDENTIAL

SPECTRAL RESPONSE CURVE
FOR TUBE NO. 86 0-203
RISE NO. 1395
DATE: 5-23-67



EUGENE DIETZEN CO.
MADE IN U. S. A.

NO. 340R-20 DIETZEN GRAPH PAPER
20 X 20 PER INCH

~~CONFIDENTIAL~~


SPECTRAL RESPONSE CURVE
FOR TUBE NO. ME-0206

RUN NO. 1199

DATE: 7-3-67

UNCLASSIFIED

~~CONFIDENTIAL~~




UNCLASSIFIED

EUGENE DIETZGEN CO.
MADE IN U. S. A.

NO. 340R-20 DIETZGEN GRAPH PAPER
20 X 20 PER INCH

~~CONFIDENTIAL~~

SPECTRAL RESPONSE CURVE
FOR TUBE NO. EX-0208
RUN NO. 1200
DATE: 7-3-67



~~CONFIDENTIAL~~

1.3 1.1 .9 .7 .5 .3

FIGURE NO. 14

UNCLASSIFIED